

CHANGE ORDER REQUEST

PROJECT: East Lawrence Rec Center

CHANGE ORDER REQUEST NUMBER:

1

CONTRACTOR: RD Johnson Excavating

DATE:

5/4/2018

The contract is changed as follows: Supply all material, labor, equipment, tools, supplies, and all temporary, preparatory and incidental work for the following items:

OPTION NO. 1: Remove & Replace 15" CMP from east existing inlet to just west of new curb & gutter = 112 LF

Tie into existing inlet with a 22 degree bend to gain added depth
 Tunnel under new curb and gutter (2 locations)
 Furnish and install 112 LF of 15" 16 Ga Aluminized CMP
 Concrete and collar connection to existing pipe west of new curb and gutter
 Install 31 SY of 6" reinforced concrete in lieu of 2" asphalt & 5" AB-3
 Credit 4 TN of 2" asphalt
 Credit 31 SY of 5" AB-3

TOTAL ITEM NO. 1 **\$ 9,444.00**

** (15" Ultra Flo is 2 week lead time, and add \$840.00)**

OPTION NO. 2: Remove & Replace 15" CMP from east existing inlet to the creek = 250 LF

Tie into existing inlet with a 22 degree bend to gain added depth
 Tunnel under new curb and gutter (2 locations)
 Furnish and install 250 LF of 15" 16 Ga Aluminized CMP
 Furnish and install 10 TN of rip rap at creek
 Install 31 SY of 6" reinforced concrete in lieu of 2" asphalt & 5" AB-3
 Credit 4 TN of 2" asphalt
 Credit 31 SY of 5" AB-3

TOTAL ITEM NO. 2 **\$ 13,493.00**

** (15" Ultra Flo is 2 week lead time, and add \$1750.00)**

The original Contract Sum was	\$ 99,489.10
Net change by previously authorized Change Orders	\$ -
The Contract Sum will be (increased/decreased) by this Change Order in the amount of	(TBD)
The new Contract Sum will be	\$ -
The Contract Time will be increased by	Days

OTHER CONDITIONS AND AGREEMENTS:

All other terms and conditions of said Contract that have not heretofore been modified shall be and remain the same.

CONTRACTOR

OWNER

